INC.

7600 N.W.79TH AVENUE

MIAMI, FLORIDA 33166

Phone: 305-592-9222

FAX: 305-594-9148

crlmiami@bellsouth.net

Report 7444-13B-FBC

15 July 2013

Tested: 9 July 2013

TESTING OF SAFTY RAILING

Client:



SĀFTRON Manufacturing, LLC 6012 33rd St E Bradenton, FL 34203- USA

Phone: (305) 233-5511, Fax: (941) 751-2802

<u>General:</u> Load tests on Steel/ PCV Plastic Safety Railings to show conformance to requirements the Florida Building Code, FBC-2010.


Witness to Testing:

Robert Weise, SĀFTRON Manufacturing, LLC George Dotzler, CRL Director of Operations

Description of Specimen: The test specimen consisted of a composite structure of PVC pipe and aluminum pipe as shown in the below referenced drawings. The test specimen was also of the nominal dimensions as shown at right (as viewed from interior side, all diagrams are similar).

Statement of Conformance: The specimen is in conformance with drawings provided by the manufacturer. These drawings have been marked to indicate the portions descriptive of these tests.

Yamil G. Kuri, P.E., Official Witness Michael Lamborghini, CRL Test Engineer



Labeled:

2200 SERIES, 6' STEEL TEST RAIL, PLATE MOUNT

Date: 5/22/2013 Sheet 1 0f 1

SĀFTRON

SĀFTRON Manufacturing, LLC 6012 33rd St E Bradenton, FL 34203- USA

Phone: (305) 233-5511, Fax: (941) 751-2802,

Reports pertain to the samples tested only and may not be reproduced without permission. Copyright 2013.

7444-13B-FBC: 15 July 2013: Page 1 of 3

1111/ 2/ 3/ 2013

7600 N.W.79TH AVENUE

as follows:

MIAMI, FLORIDA 33166

Phone: 305-592-9222

FAX: 305-594-9148

crlmiami@bellsouth.net

Test I - Load on Baluster:

A horizontal load was applied, for sixty seconds, to a 12" x 12" piece of 3/4" plywood positioned at the mid-height of the baluster (as shown in the diagram at right). Results as follows:

Code	Load (Lbs.)	Results
FBC-2010	50.0	No Failure / Passed

A single load was applied, for sixty seconds, to the mid-


span of the top rail of the specimen (as shown in the diagram at right). Deflection Gauges were placed at the top

of each post adjacent to the load and at the center of the Top Rail between the load points to record deflections.


Gauges were zeroed before each subsequent load. Results

Test II - Horizontal Point Load on Top Rail:

Tests upon Components



Tests upon Handrails and Guards




			POST	POST	Post
Code		Load (Pounds)	Defl'n / Set (In.) Top of post Lt.	Defl'n / Set (In.) Top Rail Center	Defl'n / Set (In.) Top of post Rt.
FBC-2010	200 Pounds @ mid rail	200.0	0.4375 / 0.0	1.750 / 0.1875	0.500 / 0.0

<u>Test III –Distributed Horizontal Load : Top Rail:</u>

Two equivalent and simultaneous loads were applied, for sixty seconds, to the top rail of the specimen (as shown in the diagram at right) at quarter points to simulate statically the equivalent conditions as a distributed load. Deflection Gauges were placed at the top of each post adjacent to the load and at the center of the Top Rail between the load points to record deflections. Gauges were zeroed before each subsequent load. Results as follows:

Tests upon Handrails and Guards



Code	Dist. load (PLF)	Load (Lbs.)	Total Load (Lbs.)	Defl'n / Set (In.) Top of post Lt.	Defl'n / Set (In.) Top Rail Center	Defi'n / Set (In.) Top of post Rt.
FBC-2010	50.0	150.0	300.0	0.750 / 0.0	2.0 / 0.125	0.875 /\0.0

Reports pertain to the samples tested only and may not be reproduced without permission. Copyright 201

7444-13B-FBC: 15 July 2013: Page 2 of 3

7600 N.W.79TH AVENUE

MIAMI, FLORIDA 33166


Phone: 305-592-9222

FAX: 305-594-9148

crlmiami@bellsouth.net

Test IV - Horizontal Point Load on Post:

A single load was applied, for sixty seconds, to the top of the central post of the specimen (as shown in the diagram at right). Deflection Gauges were placed at the top of this post to record deflections. Gauges were zeroed before each subsequent load. Results as follows:



Code		Load (Pounds)	Defl'n / Set (Inches) Top of post.
FBC-2010	Top Rail on Post	200.0	1.000/ 0.063
FBC-2010	Rail req. 6 Ft x 50 PLF	300.0	1.625 / 0.1875

Summary: Tests were conducted in accordance with the requirements of the Florida Building code with a safety factor of two and residual deflections at recovery of greater than or equal to 80% in all cases.

Respectfully submitted,

CONSTRUCTION RESEARCH LABORATORY, INC.

Report by Michael Lamborghini:

Test witnessed & report reviewed

by Yamil G. Kuri, P.E.:

JUL 2 3 2013